



# University of Kashmir, Srinagar

Office of the Executive Engineer, Construction Division,

No. F (Allot. ) (Elect. Int. Ext Girls Hostel) (UCD) Ku/22/859-861

Dated: 01/11/2022

Assistant Executive Engineer,  
Electric,  
University of Kashmir,  
Srinagar.

Subject: - Internal and External Electrification for 5 storeyed Girls Hostel at Main Campus.

Reference: - This Office Tender Notice No: F(Fresh)(E.Tend)(UCD)/KU/28/22 Dated: 02-09-2022.

For and on behalf of the University of Kashmir the contract for the above noted work is hereby allotted in favour of M/s Hubbi Electrical and Mechanical Engineering Prop. Hamid Mushtaq Mir S/o Mushtaq Ahmad Mir R/o Umer Colony Lal Bazar, Srinagar holding Contractor Registration No:-2120/A/2010 bearing PAN:- AMYPM8595Q and GSTIN: 01AMYPM8595Q1ZR on the rates shown below: -

Allotted cost Rs. 1,42,00,000/-  
(Rupees One Crore and Forty Two Lacs Only)  
Advertised Cost: 219.28Lacs  
Time of Completion: 12-Working Months  
Budget Head: Capex Budget

S.no	Description of Item	Quantity	Unit	Estimated rate per unit in Rupees
1	SUB DISTRIBUTION BOARD ( 2nd side) Supply, installation, testing and commissioning of L.T cubicle type totally enclosed in doortype, free standing type, dust, damp and vermin proof Main Distribution Board complete with busbars, M.V. danger notice plate, Multifunction Meter indicating lamps, CT's, interconnections, with suitable capacity aluminium leads / solid aluminium strips / rods, connection of incoming and outgoing cables with thimbles, stove enamelled painted and having following incoming and outgoing MCCB & MCB's complete as required. 1 No. 250 Amp TPN MCCB release of 36kA thermo magnetic adjustable based MCCB of 25kA , adjustable, 5 nos. 160A TPN MCCB release of 36kA with microprocessor based MCCB of 25kA , shunt trip coil, adjustable O/L, S/C, E/F release. 2nos. 125A TPN MCCB release of 36kA with Adjustable thermo magnitic and Rotary Handle. meters with of CT's R,Y,B LED phase indicating lamp with MCB protection.	1.00	Nos.	280343.00 Two Lacs Eighty Thousand Three Hundred and forty three Only

Head Draftsperson

1

Executive Engineer



REDMI NOTE 7S  
AI DUAL CAMERA

	wiring with 1.5 sq. mm PVC insulated copper wire of FRLS through heavy duty PVC conduit with all necessary accessories including providing and fixing of ceiling rose with round junction plate 5Amp switches of recessed in wall using Modular plate & MS box of required size, point taken upto D.B. duly tested and commissioned, etc. note: all items included like Conduit, Junction box, wire, box, switches etc. including wall cutting and finishing but excluding slab conduiting			One Thousand Three Hundred and Fifty Only
28	Providing and fixing of laptop/raw power point (in loop max 3 pts.) with 1.5 sq. mm PVC insulated copper wire, through PVC Conduit pipe with all necessary accessories i/c 6Amp switches, 5 Amp 3-pin socket 1 nos. recessed in wall covered with Modular Plates i/c Modular Box & MS box of required size i/c 1.5 sq.mm PVC Insulated copper wire of FRLS as earth wire, Point taken up to DB duly tested and commissioned note: all items included like Conduit, wire, box, switches etc. including wall cutting and finishing but excluding slab conduiting	340.00 ✓	POINT ✓	1400.00 One Thousand and Four Hundred Only
29	Providing and fixing of Ac points using 6 sq mm PVC FRLS insulated copper wire through 1 inch heavy duty PVC conduit pipe and providing and fixing of 32 Amp Dp MCB 10KA C curve with enclosure including providing and fixing of 6 sq. mm PVC insulated copper wire as earth wire, point taken up to D.B. duly tested and commissioned in all respects complete. note: all items included like Conduit, wire, box, switches etc. including wall cutting and finishing	2.00 ✓	EACH ✓	4500.00 Four Thousand and Five Hundred Only
30	Providing, fixing of 4 ft LED slim 16 watt 110lm/w 230V Batten type lights(T5), complete in all respects. With 2kv surge protection. commercial type	660.00 ✓	EACH ✓	610.00 Six Hundred and Ten Only
31	Providing, fixing of 12 surface LED slim 230V, complete in all respects. With 2kv surge protection. commercial type	145.00 ✓	EACH ✓	900.00 Nine Hundred Only
32	Providing, fixing of 7-9 Watt surface mount LED table light with adjustable movement angle 230V, complete in all respects. surge protection commercial type	270.00 ✓	EACH ✓	850.00 Eight Hundred and Fifty Only
33	Providing and fixing of 12"x12" Metallic type exhaust fan complete with all accessories includingd Frame etc.	36.00 ✓	EACH ✓	1450.00 One Thousand Four Hundred and Fifty Only
34	Providing and fixing of 18 inch sweep industrial Metallic type exhaust fan complete with all accessories includingd	6.00 ✓	EACH ✓	11550.00 Eleven Thousand Five Hundred and Fifty Only

Head Draftsperson

7

Executive Engineer



REDMI NOTE 7S  
AI DUAL CAMERA

	Amp. of Modular Switch, socket recessed in wall covered with modular sheet/ MS box of required size including providing and fixing of 4mm <sup>2</sup> PVC insulated copper wire as earth wire, point taken up to D.B. duly tested and commissioned, complete point in all respects note: all items included like Conduit, wire, MS box, switches etc.			
16	Installation, testing and commissioning of pre-wired, (LED) fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc as required.	26.00 ✓	EACH ✓	206.00 ✓ Two Hundred Six Only ✓
17	Supply of 4 ft LED slim16- 20 watt warm110lm/w 230V Batten type lights(T5 Type) , complete in all respects.	4.00 ✓	EACH ✓	450.00 ✓ Four Hundred Fifty Only ✓
18	Supply of 12 watt surface LED slim 230V , complete in all respects. commercial	1.00 ✓	EACH ✓	690.00 ✓ Six Hundred Ninety Only ✓
19	Supply of 15 Watt surface LED slim 230V , complete in all respects commercial	18.00 ✓	EACH ✓	1050.00 ✓ One Thousand Fifty Only ✓
20	Supply of 7-9 watt surface LED slim 230V , complete in all respects. .	3.00 ✓	EACH ✓	350.00 ✓ Three Hundred Fifty Only ✓
21	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required. Upto 450 mm sweep	2.00 ✓	EACH ✓	450.00 ✓ Four Hundred Fifty Only ✓
22	Supply, testing of 12"x12" flap window type exhaust fan complete with all accessories. etc .	2.00 ✓	EACH ✓	1550.00 ✓ One Thousand Five Hundred Fifty Only ✓
23	Supply, Installation, Testing and Commissioning of 1200 mm sweep, BEE 5 star rated, ceiling fan with Brush Less Direct Current (BLDC) Motor, class of insulation: B, 3 nos. blades, 30 cm long down rod, 2 nos. canopies, shackle kit, safety rope, copper winding, Power Factor not less than 0.9, Service Value (CM/M/W) minimum 6.00, Air delivery minimum 210 Cum/Min , 350 RPM (tolerance as per IS : 374-2019), THD less than 10%, remote or electronic regulator unit for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise=75 degree C (max.), insulation resistance more than 2 mega ohm, suitable for 230 V, 50 Hz, single phase AC Supply, earthing etc. complete as required.	4.00 ✓	EACH ✓	3730.00 ✓ Three Thousand Seven Hundred Thirty Only ✓
24	Supplying and fixing two module stepped	4.00 ✓	EACH ✓	369.00 ✓

Head Draftsperson

4

Executive Engineer



REDMI NOTE 7S  
AI DUAL CAMERA

				One Hundred Forty Five Only
02	40 mm	4.00	R.M	228.00 Two Hundred Twenty Eight Only
11	Providing and fixing of 100mm x 50mm PVC cable trunking race way of reputed make	25.00	R.M	335.00 Three Hundred Thirty Five Only
12	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.	6.00	POINT	574.00 Five Hundred Seventy Four Only
13	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc. as required. 12 Module (200mmX150mm)	1.00	EACH	547.00 Five Hundred Forty Seven Only
14	Supplying and fixing following modular switch on the existing modular plate & switch box including connections and modular plate etc. as required. 5/6 A switch	10.00	NO.	103.00 One Hundred Three Only
15	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. note: all items included like Conduit, wire, box, switches etc	2.00	POINT	1015.00 One Thousand Fifteen Only
16	Providing and fixing of Heating / AC points using 4 sq.mm PVC insulated copper wire of FRLS through 1" 2mm heavy duty PVC conduit and providing and fixing of 6/16 Amp. of Modular Switch, socket recessed in wall covered with modular sheet/ MS box of required size including providing and fixing of 4mm <sup>2</sup> PVC insulated copper wire as earth wire, point taken up to D.B. duly tested and commissioned, complete point in all respects note: all items included like Conduit, wire, MS box, switches etc.	2.00	POINT	2100.00 Two Thousand One Hundred Only
17	Supply and installation of 15 watt surface LED slim i aluminium die cast body 230V, complete in all respect with 2.5 KV surge protection and two years warranty period	10.00	EACH	1290.00 One Thousand Two Hundred Ninety Only
18	Providing and fixing modular PVC Module box with 16 A MCB and 6 pin 15/16 A	12.00	EACH	540.00 Five Hundred Forty Only

Head Draftsperson

Executive Engineer



	fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc as required.			
16	Supply of 22 watt surface LED slim i aluminium die cast body 230V, complete in all respect with 2.5 KV surge protection and two years warrenty period	16.00	EACH	2490.00 Two Thousand Four Hundred Ninety Only
17	Supply of 15 Watt surface LED slim i aluminium die cast body 230V, complete in all respect with 2.5 KV surge protection and two years warrenty period	8.00	EACH	1250.00 One Thousand Two Hundred Fifty Only
18	Supply of 7-9 watt surface LED slim 230V, complete in all respects.	2.00	EACH	350.00 Three Hundred Fifty Only
19	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required. Upto 450 mm sweep	4.00	EACH	450.00 Four Hundred Fifty Only
20	Supply, testing of 12"x12" flap window type exhaust fan complete with all accessories. etc.	4.00	EACH	1550.00 One Thousand Five Hundred Fifty Only
21	Supply, Installation, Testing and Commissioning of 1200 mm sweep, BEE 5 star rated, ceiling fan with Brush Less Direct Current (BLDC) Motor, class of insulation: B, 3 nos. blades, 30 cm long down rod, 2 nos. canopies, shackle kit, safety rope, copper winding, Power Factor not less than 0.9, Service Value (CM/M/W) minimum 6.00, Air delivery minimum 210 Cum/Min, 350 RPM (tolerance as per IS : 374-2019), THD less than 10%, remote or electronic regulator unit for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise 75 degree C (max.), insulation resistance more than 2 mega ohm, suitable for 230 V, 50 Hz, single phase AC Supply, earthing etc. complete as required.	4.00	EACH	3730.00 Three Thousand Seven Hundred Thirty Only
22	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required. 1 or 2 Module (75mmX75mm)	12.00	EACH	298.00 Two Hundred Ninety Eight Only
23	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections and modular plate etc. as required.			
23.01	15/16 A switch	6.00	NO.	156.00 One Hundred Fifty Six Only

Head Draftsperson

Executive Engineer

	as required Note: Rates of Suitable PVC conduit included in above description for the following items			
01	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	60.00 ✓	R.M	205.00 Two Hundred Five Only
02	2 x 4 sq. mm + 1 x 4 sq. mm earth wire	15.00 ✓	R.M	334.00 Three Hundred Thirty Four Only
03	2 x 6 sq. mm + 1 x 6 sq. mm earth wire	26.00 ✓	R.M	439.00 Four Hundred Thirty Nine Only
04	2 x 10 sq. mm + 1 x 10 sq. mm earth wire for Sub main wiring	26.00 ✓	R.M	570.00 Five Hundred Seventy Only
4	Supplying and fixing of following sizes of heavy class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. 25 mm	171.00 ✓	R.M	110.00 One Hundred Ten Only
5	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. note: all items included like Conduit wire, box, switches etc	56.00 ✓	POINT	1015.00 One Thousand Fifteen Only
6	Providing and fixing of Heating points using 4 sq. mm PVC insulated copper wire of FRLS through 1" 2mm heavy duty PVC conduit and providing and fixing of 6/16 Amp. of Modular Switch, socket recessed in wall covered with modular sheet/ MS box of required size including providing and fixing of 4mm <sup>2</sup> PVC insulated copper wire as earth wire, point taken up to D.B. duly tested and commissioned, complete point in all respects note: all items included like Conduit, wire, MS box, switches etc.	4.00 ✓	POINT	2100.00 Two Thousand One Hundred Only
7	Installation, testing and commissioning of Pre-wired (LED) fluorescent fitting / fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc as required.	33.00 ✓	EACH	206.00 Two Hundred Six Only
8	Supply of 15 Watt surface LED slim 230V, complete in all respects commercial	30.00 ✓	EACH	1050.00 One Thousand Fifty Only
9	Supply of 7-9 watt surface LED slim 230V complete in all respects.	2.00 ✓	EACH	350.00 Three Hundred Fifty Only
10	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	16.00 ✓	EACH	369.00 Three Hundred Sixty Nine Only

Head Draftsperson

2

Executive Engineer

04	2 x 6 sq.mm + 1 x 6 sq.mm earth wire	20.00 ✓	R.M ✓	1.00 ✓ Rupee One Only ✓
4.05	2 x 10 sq.mm + 1 x 10 sq.mm earth wire for Sub main	30.00 ✓	R.M ✓	200.00 ✓ Two Hundred Only ✓
5.00	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. 25 mm	60.00 ✓	R.M ✓	10.00 ✓ Ten Only ✓
6.00	Providing and fixing of Heating points using 4 sq.mm PVC insulated copper wire of FRLS through medium class PVC conduit and providing and fixing of 6/16 Amp. of Modular Switch, socket recessed in wall covered with modular sheet/ MS box of required size including providing and fixing of 4mm <sup>2</sup> PVC insulated copper wire as earth wire, point taken up to D.B. duly tested and commissioned, complete point in all aspects Note: All items included like Conduit, wire, MS box, switches, including cutting and finishing etc.	4.00 ✓	POINT ✓	2000.00 ✓ Two Thousand Only ✓
7.00	Providing and fixing of Lighting point wiring with 1.5 mm <sup>2</sup> PVC insulated copper wire of FRLS through heavy duty PVC conduit pipe with all necessary accessories including providing and fixing of ceiling rose with round junction plate 5Amp switches of recessed in wall using Modular switches, plate & MS box of required size, point taken upto D.B. duly tested and commissioned, etc. note: all items included like Conduit, MS junction box, wire, box, switches, ceiling rose etc.	9.00 ✓	POINT ✓	1000.00 ✓ One Thousand Only ✓
8.00	Providing and fixing of fan/ light point wiring with 1.5 sq. mm PVC insulated copper wire of FRLS through heavy duty PVC conduit with all necessary accessories including providing and fixing of ceiling rose with round junction plate 5Amp switches of recessed in wall using Modular plate & MS box of required size, point taken upto D.B. duly tested and commissioned, etc. note: all items included like Conduit, Junction box, wire, box, switches, ceiling rose etc.	3.00 ✓	POINT ✓	300.00 ✓ Three Hundred Only ✓
9.00	Providing and fixing of ups/laptop/raw power point (in loop max 3 pts.) with 1.5 sq. mm PVC insulated copper wire, through PVC Conduit pipe with all necessary accessories i/c 6Amp switches, 5 Amp 3-pin socket 1 nos. recessed in wall covered with Modular Plates i/c Modular Box & MS box of required size i/c 1.5 sq.mm PVC Insulated copper wire of FRLS as earth wire, Point taken up to DB duly tested and commissioned note: all items included like Conduit, wire, box, switches, including cutting and finishing etc.	22.00 ✓	POINT ✓	800.00 ✓ Eight Hundred Only ✓
10.00	Providing/fixing of 4 ft LED slim 20 watt 110lm/w 230V Batten type lights(T5), complete in all respects. With 2kv surge protection. Industrial	9.00 ✓	EACH ✓	350.00 ✓ Three Hundred Fifty Only ✓
11.00	Providing and fixing of 48 inches Sweep energy efficient ceiling fan of approved sample at site including wiring the down rods of standard length (30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. including Fan Junction MS box as required	3.00 ✓	EACH ✓	2100.00 ✓ Two Thousand One Hundred Only ✓

Head Draftsperson

Executive Engineer

10.00	Providing and fixing of Ac points using 6 sq mm PVC FRLS insulated copper wire through 1 inch heavy duty PVC conduit pipe and providing and fixing of 32 Amp Dp MCB 10KA C curve with enclosure including providing and fixing of 6 sq. mm PVC insulated copper wire as earth wire, point taken up to D.B. duly tested and commissioned in all respects complete. note: all items included like Conduit, wire, box, switches, cutting the wall and making good the same etc.	6.00 ✓	EACH ✓	3000.00 ✓ Three Thousand Only ✓
11.00	Providing, fixing LED slim 15 watt 230V Downlighter Recessed/ Surface mount including MS box of required size as per requirement, complete in all respects not less than 100 LM/W LM79-80, L70 2KV Surge Protection	22.00 ✓	EACH ✓	1200.00 ✓ One Thousand Two Hundred Only ✓
12.00	Providing, fixing LED slim 20 Watt T5 230 V 50 HZ.	4.00 ✓	EACH ✓	1000.00 ✓ One Thousand Only ✓
13.00	Providing and fixing of 48 inches Sweep energy efficient ceiling fan of approved sample at site including wiring the down rods of standard length (30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc including Fan Junction MS box as required.	4.00 ✓	EACH ✓	2200.00 ✓ Two Thousand Two Hundred Only ✓
14.00	Providing and fixing of 24 inches Sweep energy efficient wall fan of approved sample at site including wiring complete in all respects	5.00 ✓	Nos. ✓	3200.00 ✓ Three Thousand Two Hundred Only ✓
15.00	supplying, fixing of MS fan extension rod with holes, nuts, bolts etc as required 2 ft length with fan holding hook arrangements as per site requirement.	6.00 ✓	EACH ✓	1.00 ✓ One Rupee Only ✓
16.00	Providing and fixing of Fan dimmer electronic regulator Including MS box and Modular Plate 5Ampere 3 pin type.	6.00 ✓	EACH ✓	1.00 ✓ One Rupee Only ✓
17.00	Supplying and fixing of following sizes of heavyduty class conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required. 20 mm.	30.00 ✓	R.M ✓	1.00 ✓ One Rupee Only ✓
18.00	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required. 1 or 2 Module (75mmX75mm)	4.00 ✓	Nos. ✓	1.00 ✓ One Rupee Only ✓
19.00	Dismantaling of old electric wiring of the site as required.	1.00 ✓	JOB ✓	1.00 ✓ One Rupee Only ✓
20.00	4 Module (125mmX75mm)	4.00 ✓	Nos. ✓	1.00 ✓ One Rupee Only ✓
21.00	Supply of advance maintenance free Chemical Gel Earthing of Dual Pipe Technology (GI) of 3 mtrs long 80 mm dia of outer shell (MS) with the 50 mm dia of inner shell (MS) of 80-100 microns galvanized CHEMRODE filled with highly conducting metallic compounds with the permanent sealings at both the ends with the lead terminal of 50x10mm size at the top. The electrode shall be duly tested and certified by CPRI (Central Power Research Institute), Govt of India for a peak short circuit withstanding capacity	2.00 ✓	EACH ✓	8000.00 ✓ Eight Thousand Only ✓

	Switch, socket recessed in wall covered with modular sheet/ MS box of required size including providing and fixing of 4mm <sup>2</sup> PVC insulated copper wire as earth wire, point taken up to D.B. duly tested and commissioned, complete point in all aspects note: all items included like Conduit, wire, MS box, switches etc.			
12	Providing and fixing of Lighting point wiring with 1.5 mm <sup>2</sup> PVC insulated copper wire of FRLS through heavy duty PVC conduit pipe with all necessary accessories including providing and fixing of ceiling rose with round junction plate 5Amp switches of recessed in wall using Modular switches, plate & MS box of required size, point taken upto D.B. duly tested and commissioned, etc. note: all items included like Conduit, MS junction box, wire, box, switches etc.	25.00	POINT	1150.00 One Thousand One Hundred Fifty Only
13	Providing and fixing of fan point wiring with 1.5 sq. mm PVC insulated copper wire of FRLS through heavy duty PVC conduit with all necessary accessories including providing and fixing of ceiling rose with round junction plate 5Amp switches of recessed in wall using Modular plate & MS box of required size, point taken upto D.B. duly tested and commissioned, etc. note: all items included like Conduit, Junction box, wire, box, switches etc.	8.00	POINT	1350.00 One Thousand Three Hundred Fifty Only
14	Providing and fixing of 15 surface LED slim 230V, complete in all respects. With 2kv surge protection commercial type	4.00	EACH	1200.00 One Thousand Two Hundred Only
15	Providing, fixing of T5 20W LED slim 230V, complete in all respects. With 2kv surge protection.	16.00	EACH	610.00 Six Hundred Ten Only
16	Providing and fixing of 12"x12" Metallic type exhaust fan complete with all accessories including Frame etc.	4.00	EACH	1450.00 One Thousand Four Hundred Fifty Only
17	Providing and fixing of 48 inches Sweep energy efficient ceiling fan of approved sample at site including wiring the down rods of standard length (30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc including Fan Junction MS box as required.	7.00	EACH	2300.00 Two Thousand Three Hundred Only
18	Providing and fixing of Fan down rods upto 3ft long	7.00	Nos	530.00 Five Hundred Thirty Only
19	Providing and fixing of Fan dimmer electronic regulator Including MS box and Modular Plate 5Ampere 3 pin type.	7.00	EACH	520.00 Five Hundred Twenty Only
20	Supply of advance maintenance free Chemical Gel Earthing of Dual Pipe Technology (GI) of 3 mtrs long 80 mm dia of outer shell (MS) with the 50 mm dia of inner shell (MS) of 80-100 microns galvanized CHEMRODE filled with highly conducting metallic compounds with the permanent sealings at both the ends with the lead terminal of 50x10mm size at the top. The electrode shall be duly tested and certified by CPR (Central Power Research Institute), Govt	2.00	EACH	21500.00 Twenty One Thousand Five Hundred Only

Head Draftsperson

3

Executive Engineer



REDMI NOTE 7S  
AI DUAL CAMERA



**University of Kashmir, Srinagar**  
**Office of the Executive Engineer, Construction Division,**

No. F (UCD) (Elec. Works 4 storeyed Resch. Hostel ZC)(UCD) Ku/22/733-735 Dated: 16/06/2022

Assistant Executive Engineer,  
Electric,  
University of Kashmir,  
Srinagar.

Subject: - Electrical and allied works for 04-Storeyed Research Hostel at Zakura Campus (Balance Work).

Reference: - This Office Tender Notice No: - F(E.Tend)(UCD)/KU/02/22

DATED: - 12-04-2022.

For and on behalf of the University of Kashmir the contract for the above noted work is hereby allotted in favour of  
M/s F.M Infrastructure Builders Private Limited Prop. Wakar Ahmad Bhat S/o R/o Summerbugh,  
Lasjan, Srinagar holding Contractor Registration No: - 5632-A/2022 bearing PAN: - AAECF4409M and  
GSTIN: 01AAECF4409M1ZT on the rates shown below: -

Allotted Cost: - Rs. 30,30,188.00/-  
(Rupees Thirty Lacs Thirty Thousand One Hundred Eighty Eight Only)  
Advertised Cost: Rs. 42.13 Lacs  
Time of Completion: - 04-Months

S.no	Description of Item	Quantity	Unit	Allotted rate per unit in Rupees
1.00	EXETRNAL FEEDER PILLER NON DSR ITEMS Supply, installation, testing and commissioning of outdoor type External Feeder Pillar complete with busbars, M.V. danger notice plate, Multifunction Meter indicating lamps, CT's, interconnections, with suitable capacity aluminium leads / solid aluminium strips / rods, connection of incoming and outgoing cables, with following material in each as per Single line diagram complete as required in cement foundation complete. (MR) "EXTERNAL FEEDER PILLAR(TYPE-1) shall consists of : Note : Enclosure should be IP54 protected " INCOMER 1No., 63 Amps DP (15kA) MCB (Icu) having IP 20 Protection, CE Approved, Applicable BIS Standards (ISI mark, IS 8828-1996, IEC 898) "Indicating lamps (LED) with protection MCB for Incomer i) ON, OFF, Trip indication. ii) RYB indication." Voltmeter, Ammeter and KWH with 1 set of CT's of 125/5 Amp. BUSBAR 63 Amp DP busbars of aluminium alloy. TIMER 1 No. 40A Digital, 365 Days, 24 HRS. Programmable astronomical timer with suitable contactor. OUTGOINGS 10 nos. 25 AMPS SP MCB( C- Curve), 10KA for Light Circuit having IP 20 Protection, CE Approved, Applicable BIS Standards	1.00	SET	79000.00 Seventy Nine Thousand Only

Head Draftsperson

1

Executive Engineer

2.00	LIGHT NON DSR Providing and Fixing of lighting fixture pressure die-cast aluminium IP66 roadway luminaire with high power LED(30W) as light source with toughened glass applicable BIS Standards and ISI Marks etc. Certification: LM79-08, LM80, L70, NABL etc.	40.00	Nos.	1900.00 ✓ One Thousand Nine Hundred Only ✓
3.00	Providing and fixing of 0.75meter long MS Painted outdoor luminary arms for holding 1 no luminary and duly fitted on the pole with clean Welding job i/c Supplying/Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/ steel works and anti-corrosive Bitumastic paint of approved brand and manufacture to give an even shade. two or more coats work as per requirement.	40.00 ✓	Nos. ✓	2999.00 ✓ Two Thousand Nine Hundred Ninety Nine Only ✓
4.00	LT NON DSR Supply of ISI marked aluminium conductor XLPE insulated cable as per IS 7098, armoured, served, sheathed 1100 volts grade. having ISO 9001/14001 marks etc.			
4.01	(MR) 16 sqmm 2 core	1200.00 ✓	R.M. ✓	159.00 ✓ One Hundred Fifty Nine Only ✓
4.02	(MR) 50 sqmm 2 core	30.00 ✓	R.M. ✓	370.00 ✓ Three Hundred Seventy Only ✓
5.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation and refilling the trench etc as required. Upto 35 sq. mm	1180.00 ✓	R.M. ✓	99.00 ✓ Ninety Nine Only ✓
6.00	EARTHING & MISCELLANEOUS ITEMS DSR (DSR 5.4) "Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required. Note:-Described item only for earthing of Feeder Pillar." Point taken upto desired panel	2.00 ✓	Nos. ✓	3500.00 ✓ Three Thousand Five Hundred Only ✓
7.00	(MR) Supply of advance maintenance free Chemical Gel Earthing of Single Pipe Technology of 3mtrs length 60-63 mm dia CHEMRODE filled with highly conducting metallic compounds with the permanent sealings at the both the ends. Top of the earth electrode shall be compressed to form an extended lead with 2 holes for connected the strip/wire to the load. Point taken upto desired panel	1.00 ✓	Nos. ✓	6500.00 ✓ Six Thousand Five Hundred Only ✓
8.00	Supply of environment friendly rust proof heavy duty weather proof polyplastic earth pit chamber.	3.00 ✓	Nos. ✓	2000.00 ✓ Two Thousand Only ✓
9.00	MISCELLANEOUS D.S.R.ITEMS (DSR 2.21) Providing and fixing M.V. danger notice plate of 200mmx150mm made of mild steel, atleast 2mm thick and vitreous enamelled white on both sides and with inscription single red colour on front side as required.	2.00 ✓	Nos. ✓	500.00 ✓ Five Hundred Only ✓
10.00	Supply, laying, jointing, testing and commissioning of ISI marked (IS : 14930, part 2) H.D.P.E. (DWC) Double wall Corrugated pipe for cable laying having corrugation on outer wall and plain smooth surface at inner side including transportation upto the site, jointing, providing and fixing all fittings i.e. sockets, couplers, reducers, end caps etc to complete the works in all respects.			
10.01	(MR) 50 mm OD	80.00 ✓	R.M. ✓	149.00 ✓ One Hundred Forty Nine Only ✓

Head Draftsperson

2

Executive Engineer

	include with the above item.			
20.00	Providing and fixing of 2 row frame structure to accommodate 4 flood lights of M.S. Pipe of suitable diameter to fit on pole with bolts keeping opening for cable entry duly painted with minimum coating of 10 micron to be kept at suitable angle i/c Supplying/Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/ steel works and anti-corrosive Bitumastic paint of approved brand and manufacture to give an even shade, two or more coats work as per requirement, having clean welds	4.00 ✓	Nos. ✓	6500.00 ✓ Six Thousand Five Hundred Only
21.00	Providing and Fixing of lighting fixture pressure die-cast aluminium IP66 roadway luminaire with high power LED(120W)with toughened glass	16.00 ✓	Nos. ✓	5999.00 ✓ Five Thousand Nine Hundred Ninety Nine Only
22.00	Supplying, Installation, Testing and Commissioning of Silent Diesel Generator Set 50 kVA, 3 Phase, 50 Hz Air Cooled Silent DG Set comprising of Air cooled Diesel Engine & Alternator rated at Three Phase, 415V, 50 Hz both mounted and aligned on a common MS base frame complete with manual panel, fuel tank, Residential Exhaust Silencer, 12 V battery, AVM Pad, Maintenance Free Battery lead fitted in Sound Proof acoustic enclosure approved by CPCB. Governing class (As per ISO 8528 Part-V), Noise level <75 dBA, Rated output :Prime Continuous rating as per ISO 8528-1, 1500RPM/50Hz, Alternator Insulation Class H, Voltage Reg: +-1%	1.00 ✓	Nos. ✓	530000.00 ✓ Five Lakh Thirty Thousand Only
23.00	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	4.00 ✓	Nos. ✓	3000.00 ✓ Three Thousand Only
24.00	Supplying and laying 25 mm X 5 mm G.I strip at 0.50 metre below ground as strip earth electrode, including connection/ terminating with G.I. nut, bolt, spring, washer etc. as required. (Joining shall be done by overlapping and with 2 sets of G.I. nut bolt & spring washer spaced at 50mm)	20.00 ✓	R.M. ✓	150.00 ✓ One Hundred Fifty Only
25.00	Constructing of masonry Chamber 100x100x100 cm, inside with 75 class designation brick work in cement moryar 1:5 ( 1 cement : 5 fine sand ) for valve, with C.I.surface box 100mm top diameter, 160mm bottom diameter and 180mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) necessary excavation foundation concrete 1:5:10 ( 1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand ) 12mm thick finished with a floating coat of neat cement complete as per standard design (NOTE: Actual Depth of chamber may vary as per Site conditions).	4.00 ✓	Nos. ✓	3500.00 ✓ Three Thousand Five Hundred Only
26.00	Supply, Installation, Testing and Commissioning of 20 kVA servo stabilizer Digital Microcontroller Buck booster Servo Voltage Stabilizer 3 phase 4 wire out-door Radiator type (3 phase: 230 V to 460 V input and 415 V Out put) of with fresh dehydrated oil. With protection, complete in all respects.(Specifications are attached) 1. High & low voltage Cut off 2. Over current protection, SC Protection Cooling:- ONAN 3. Time delay protection	1.00 ✓	Nos. ✓	149000.00 ✓ One Lakh Forty Nine Thousand Only
27.00	Supplying/transportation/insurance/ installation/testing/ commissioning of pilfer resistant 11KV metering Kiosk suitable for housing Resin cast CT, PT and bi-directional Tri-vector meter fabricated out of MS Sheet steel of thickness not less than 2mm duly powder coat painted. The foundation base should be of MS channel iron not less than 100mmx50mmx6mm should be suitably grouted in M15 cement concrete. it should have two	1.00 ✓	SET ✓	78000.00 ✓ Seventy Eight Thousand Only

Head Draftsperson

4

Executive Engineer





# University of Kashmir, Srinagar

Office of the Executive Engineer, Construction Division,

No. F ( 670 ) ( Epec for Police Barrack (KUG COY) ) (UCD) Ku/20/133-135 Dated: -25/11/2020

Assistant ~~Executive~~ Engineer,  
University of Kashmir,  
Srinagar.

Subject: - Electrification for Police Barrack (KUG COY Police Line) outside University Campus.

Reference: - This Office Tender Notice No: F (E.Tend) (UCD) KU/ 12/20 DATED: -16-10-2020.

For and on behalf of the University of Kashmir the contract for the above noted work is hereby allotted in favour of M/s Wani Electric and Mechanical Engineers Prop. Mohammad Saleem Wani R/o Hazratbal Srinagar Registration No. 3837/A/2017 having PAN: AEWPW6612C and GST: 01AEWPW6612C1ZF on the rates shown below:-

Allotted Cost: - Rs.1,38,522/-  
(Rupees One Lac Thirty Eight Thousand Five Hundred and Twenty Two Only)  
Time of Completion: - 01-Month

S.no	Description of Item	Quantity	Unit	Allotted rate per unit in Rupees
1.00	Supply, installation, testing and commissioning of sub main control M.V. cubicle type totally enclosed (double door type) wall mount type, dust, damp and vermin proof M.V. danger notice plate, connection of incoming and outgoing cables with thimbles, stove enameled painted and having following incoming/ outgoing MCCB, meters, indicators and bus bar arrangements complete as required. with extra space for MCCB/ MCB's a) 1no. 160 Amp. 4pole 25KA of Siemens/ABB / legarnd make b) 1 set 160 Amp busbar 4 strip heavy duty aluminum basbar. c) 0-500volt volt meter (digital) d) Phase selector switches.	1.00	NO.	35000.000 Thirty Five Thousand Only
2.00	Supply of ISI marked aluminium conductor XLPE insulated cable as per IS 7098, armoured, served, sheathed 1100 volts grade. Havells/ Finolex 50 sqmm 3 1/2 core	50.00	RNM	350.000 Three Hundred and Fifty Only
3.00	Supplying and making end termination with brass compression glands of following sizes of 1.1. kv grade multicore aluminium conductor PVC insulated and PVC sheathed 3 1/2 X 50 sq. mm (38mm)	2.00	NO.	50.000 Fifty Only
4.00	Laying of one number additional PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground in the same trench in one run horizontal formation including excavation, sand cushioning, protective covering and refilling the trench etc as required. Above 35 sq. mm and upto 95 sq. mm	50.00	RNM	10.000 Ten Only
5.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	20.00	RNM	50.000 Fifty Only

Head Draftsperson

1

Executive Engineer



REDMI NOTE 7S  
AI DUAL CAMERA



	wall using Modular switches, plate & MS box of required size, point taken upto D.B. duly tested and commissioned, etc. note: all items included like Conduit, MS junction box, wire, box, switches etc. and wall cutting and finishing also included			
00	Providing and fixing of fan/ light point wiring with 1.5 sq. mm PVC insulated copper wire of and fixing through heavy duty PVC conduit with plate 5A necessary accessories including providing Modular fixing of ceiling rose with round junction taken at 5Amp switches of recessed in wall using modular plate & MS box of required size, point taken upto D.B. duly tested and commissioned, etc. note: all items included like Conduit, Junction box, wire, box, switches etc. including wall cutting and finishing etc in all respects	44.00 ✓	POINT ✓	797.00 ✓ Seven Hundred Ninety Seven Only
2 00	Providing and fixing of UPS point (in loop max 5 pts.) with 1.5 sq. mm PVC insulated copper wire, through PVC Conduit pipe with all necessary accessories i/c 5Amp switches, 5 Amp 3-pin socket 1 nos. recessed in wall covered with Modular Plates i/c Modular Box & MS box of required size i/c 1.5 sq. mm PVC Insulated copper wire of FRLS as earth wire, Point taken up to DB duly tested and commissioned note: all items included like Conduit, wire, box, switches etc. including wall cutting and finishing etc in all respects	65.00 ✓	POINT ✓	797.00 ✓ Seven Hundred Ninety Seven Only
13.00	Providing and fixing of Ac points using 6 sq mm PVC FRLS insulated copper wire through 1 inch heavy duty PVC conduit pipe and providing and fixing of 32 Amp Dp MCB 10KA C curve with enclosure including providing and fixing of 6 sq. mm PVC insulated copper wire as earth wire, point taken up to D.B. duly tested and commissioned in all respects complete. note: all items included like Conduit, wire, box, switches etc. including wall cutting and finishing etc in all respects	24.00 ✓	EACH ✓	3226.00 ✓ Three Thousand Two Hundred Twenty Six Only
14.00	Providing, fixing of 4ft 20 watt LED slim 16 watt 230V T5 tube light type Surface mount, complete in all respects not less than 110 LM/W LM79-80, L70, 2.5KV Surge Protection	16.00 ✓	EACH ✓	326.00 ✓ Three Hundred Twenty Six Only
15.00	Providing, fixing LED slim 15 watt 230V Downlighter Recessed/ Surface mount including MS box of required size as per requirement, complete in all respects not less than 100 LM/W LM79-80, L70 2KV Surge Protection	88.00 ✓	EACH ✓	737.00 ✓ Seven Hundred Thirty Seven Only
16.00	Providing, fixing LED slim 12 watt 230V Downlighter Recessed/ Surface mount including MS box of required size as per requirement, complete in all respects not less than 100 LM/W LM79-80, L70 2KV Surge Protection	25.00 ✓	EACH ✓	397.00 ✓ Three Hundred Ninety Seven Only
17.00	Providing and fixing of 12"x12" Metallic type exhaust fan complete with all accessories including Frame etc.	12.00 ✓	EACH ✓	997.00 ✓ Nine Hundred Ninety Seven Only
18.00	Providing and fixing of 48 inches Sweep energy efficient ceiling fan of approved sample at site including wiring the down rods	24.00 ✓	EACH ✓	1326.00 ✓ One Thousand Three

Head Draftsperson

Executive Engineer





# University of Kashmir, Srinagar

Office of the Executive Engineer, Construction Division

External Elect. Zakura

No. F ( ) ( ) UCD/Ku/16/25-28

Dated: 9/6/2016

Assistant Engineer,  
University of Kashmir  
Srinagar

**Subject:-** External Electrification for Zakura Campus by way of Supply, Installation, Testing and Commissioning of Street Light and other Electric works)

**Reference:-** This office Tender Notice No.F(E.Tend)(Electric works Zakura)UCD/50/15 Dated:-28-10-2015

For and on behalf of the University of Kashmir the contract for the above noted work is hereby allotted in favour of **M/s Associate Engineers Prop. Mohd Ashraf Hakeem r/o Auqaf Building Budshah Chowk, Srinagar holding Contractor Registration 1938/A/2009** bearing PAN **AELPH-6233-D** & having **TIN 01732083487** on the rates shown below.

Allotted cost Rs.23,16,665/-

(Rupees Twenty Three Lacs Sixteen Thousand Six Hundred and Sixty Five Only)

Time of completion:- 1-Month

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Allotted rate per Unit in Rupees
1.	EXETRNL FEEDER PILLER NON DSR ITEMS Supply, installation, testing and commissioning of outdoor type External Feeder Pillar complete with busbars, M.V. danger notice plate, Multifunction Meter indicating lamps, CT's, interconnections, with suitable capacity aluminium leads / solid aluminium strips / rods, connection of incoming and outgoing cables, with following material in each as per Single line diagram complete as required. (MR) "EXTERNAL FEEDER PILLAR(TYPE-1) shall consists of : Note : Enclosure should be IP54 protected " INCOMER 1No., 125 Amps TPN (15kA) MCCB (Icu ) with thermal Magnetic based release "Indicating lamps (LED) with protection MCB for Incomer i) ON, OFF, Trip indication. ii) RYB indication." Voltmeter, Ammeter and KWH with 1 set of CT's of 125/5 Amp. BUSBAR 125 Amp TPN busbars of aluminium alloy. TIMER 1 No. 40A Digital, 365 Days, 24 HRS. Programmable timer with suitable contactor. OUTGOINGS	2.00	SET	@ Rs.69000/Set (Rupees Sixty Nine Thousand per Set only)

Head Draftsman

Page 1 of 4

Executive Engineer

	1 no. 40 AMPS TPN MCB( D- Curve), 10KA 3 no. 40 AMPS DP MCB( C- Curve), 10KA 18 nos. 10 AMPS SP MCB( C- Curve), 10KA for Light Circuit 2 no. 63 AMPS TPN MCCB, 15KA Spare Feeder			
2.	(MR) "EXTERNAL FEEDER PILLAR(TYPE-2) shall consists of : Note : Enclosure should be IP54 protected " INCOMER 1No., 63 Amps TPN (15kA) MCCB (Icu ) with thermal Magnetic based release "Indicating lamps (LED) with protection MCB for Incomer i) ON, OFF, Trip indication. ii) RYB indication." Voltmeter, Ammeter and KWH with 1 set of CT's of 125/5 Amp. BUSBAR 63 Amp TPN busbars of aluminium alloy. TIMER 1 No. 40A Digital , 365 Days, 24 HRS. Programmable timer with suitable contactor. OUTGOINGS 1 no. 40 AMPS TPN MCB( D- Curve), 10KA 3 no. 40 AMPS DP MCB( C- Curve), 10KA 18 nos. 10 AMPS SP MCB( C- Curve), 10KA for Light Circuit 3 no. 20 AMPS DP MCB( D- Curve), 10KA 1 no. 40 AMPS TPN MCB( D- Curve), 10KA	1.00 ✓	SET ✓	@ Rs.71000/Set ✓ (Rupees Seventy One Thousand per Set only) ✓
3.	LIGHT FIXTURES NON DSR ITEMS "Supply of Decorative spherical shape post top lantern suitable for single retrofit LED Lamp of 40W, in polycarbonate housing Luminare is Suitable for post/ pole mounting of 60mm dia (max.) Note: Cost shall include Lamp , Electric Gear & other accessories required to commission the product." (MR) Make: PHILIPS, 40W LED or Equivalent	145.00 ✓	Nos ✓	@ Rs.3800/No. ✓ (Rupees Three Thousand and Three Hundred per No. only) ✓
4.	LT CABLE NON DSR ITEMS Supply of ISI marked aluminium conductor XLPE insulated cable as per IS 7098, armoured, served, sheathed 1100 volts grade. (MR) 6 sqmm 3 core	2800.00 ✓	RM ✓	@ Rs.160/RM ✓ (Rupees One Hundred and Sixty per RM only) ✓
5.	(MR) 25 sqmm 3 1/2 core	200.00 ✓	RM ✓	@ Rs.223/RM ✓ (Rupees Two Hundred and Twenty Three per RM only) ✓
6.	(MR) 50 sqmm 3 1/2 core	180.00 ✓	RM ✓	@ Rs.10/RM ✓ (Rupees Ten per RM only) ✓
7.	EARTHING & MISCELLANEOUS DSR ITEMS (DSR 5.4) "Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre	3.00 ✓	Nos ✓	@ Rs.9000/No. ✓ (Rupees Nine Thousand per No. only) ✓

Head Draftsman

Page 2 of 4

Executive Engineer



REDMI NOTE 7S  
AI DUAL CAMERA

	long etc. with charcoal/ coke and salt as required. Note:-Described item only for earthing of Feeder Pillar."			
8.	(DSR 6.2) Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, G.I. tube, having single prong at top, with 85 mm dia 6 mm thick G.I. base plate including holes etc. complete as required.	4.00 ✓	Nos	@ Rs.2000/No. (Rupees Two Thousand per No. only) ✓
9.	(MR) Supply of advance maintenance free Chemical Gel Earthing of Single Pipe Technology (Copper) of 3mtrs length 60-63 mm dia CHEMRODE filled with highly conducting metallic compounds with the permanent sealings at the both the ends. Top of the earth electrode shall be compressed to form an extended lead with 2 holes for connected the strip/wire to the load.	2.00 ✓	Nos ✓	@ Rs.15000/No. (Rupees Fifteen Thousand per No. only) ✓
10.	Supply of environment friendly rust proof heavy duty weather proof polyplastic earth pit chamber.	4.00 ✓	Nos ✓	@ Rs.350/No. (Rupees Three Hundred and Fifty per No. only) ✓
11.	SECTION 7 MISCELLANEOUS D.S.R.ITEMS (DSR 2.21) Providing and fixing M.V. danger notice plate of 200mmx150mm made of mild steel, atleast 2mm thick and vitreous enamelled white on both sides and with inscription single red colour on front side as required.	3.00 ✓	Nos ✓	@ Rs.260/No. (Rupees Two Hundred and Sixty per No. only) ✓
12.	MISCELLANEOUS NON DSR ITEMS (MR) Supplying and laying of 1000 mm wide x 12 mm thick chequered rubber matting of tested quality to withstand 15KV dielectric strength as per IS 5424 : 1969 complete in all respects.	6.00 ✓	Nos ✓	@ Rs.260/No. (Rupees Two Hundred and Sixty per No. only) ✓
13.	(MR) S/F of shock treatment chart (prescribed under I.E.rules) duly framed with glass and supported from back with hard board with supply of all material labour T & P etc for proper completion of work. (Approx front area = 1.20 sq M)	3.00 ✓	Nos ✓	@ Rs. 2600/RM (Rupees Two Thousand and Six Hundred per RM only) ✓
14.	Supply, laying, jointing, testing and commissioning of ISI marked (IS : 14930, part 2) H.D.P.E. (DWC) Double wall Corrugated pipe for cable laying having corrugation on outer wall and plain smooth surface at inner side including transportation upto the site, jointing, providing and fixing all fittings i.e. sockets, couplers, reducers, end caps etc to complete the works in all respects. (MR) 100 mm. ID / 120 mm OD	10.00 ✓	RM ✓	@ Rs.650/RM (Rupees Six Hundred and Fifty per RM only) ✓
15.	(MR) 175 mm. ID / 210 mm OD	10.00 ✓	RM ✓	@ Rs.800/Each (Rupees Eight Hundred Each) ✓
16.	Providing & fixing carbon dioxide(CO2) type fire extinguishers conforming to IS 2878 : 1976 and cylinders fully charged of following capacity. (MR) 4.5 KG	3.00 ✓	EACH ✓	@ Rs.4000/Each (Rupees Four Thousand Each) ✓

Head Draftsman

Page 3 of 4

Executive Engineer

17.	(MR) Supply & fixing of fome fire extinguishers, portable type 9 lit capacity hanged on wall with bracket complete as required.	3.00	EACH	@ Rs.5000/Set (Rupees Five Thousand per Set only)
18.	(MR) Providing of set of 4 nos. 9.5 Litre capacity GI bucket painted in post office red colour with prior cost of red oxide paint 'FIRE' and mounted on MS angle iron frame with bracket of appropriate size & capacity i/c filling sand etc.	3.00	SET	@ Rs.5000/Each (Rupees Five Thousand per Each only)
19.	(MR) Providing First Aid Box as approved by St.Jhon Ambulance Bridge/Indian Red Cross conforming to IS 2217 : 1963.	1.00	EACH	@ Rs.725/No. (Rupees Seven Hundred and Twenty Five per No. only)
20.	(MR) Design, fabrication, supplying to site of installation, preparing foundations, installing in position, testing and commissioning of 4 M height above ground level M.S. Tubular steel poles of 100 mm dia steel pipe with suitable size of reducer for fixing light fixture. The cost of 2x1.5 sq mm copper insulated PVC wire from Jn. box (given above) shall also be included alongwith 14 SWG copper wire. The pole would be duly grouted in the ground with 1:3:6 cement, concrete and sand mixture. It would be dule painted with rust proof silver paint.Item also include IP 65 or equivalent Cable Junction Box for poles with 2A DP MCB & 6sq mm terminal block with water tight cover and suitable cable entry space as per requirement and standard design. Note:-(i)Cost of termination of incoming and outgoing cable in pole box shall be include with the above item.	145.00	Nos	@ Rs.6300/Meter (Rupees Six Thousand and Three Hundred per Meter only)
21.	(MR) Providing & Laying in position, alignment, jointing etc RCC hume pipes 300mm dia of NP2 class for culverts, road crossing, including cutting, collars jointing etc all complete as per specifications, drawing and direction of EIC. Excavation, backfilling, PCC 1:5:10 (1 Cement: 5 Fine aggregate: 10 Coarse aggregates) around the pipe to be included in rates.	50.00	Mtrs	@ Rs.300/Meter (Rupees Thee Hundred per Meter only)

Head Draftsman

Executive Engineer

Note:-

1. The Contractor be directed to produce his enlistment card for necessary entry therein and for drawl of agreement with the university.
2. The rates mentioned above are inclusive of all carriage, income tax, sales tax and Service tax etc.
3. The date of start for the work shall be reckoned from 13/06/2016
4. The contractor has deposited CDR for an amount of Rs. Rs. 10000/- bearing No:- 2546065 dated:- 13/06/2016.
5. All other terms and conditions as per NIT shall be binding upon the contractor.
6. No change of specification is allowed in any case.
7. The works register complete in all respects shall be maintained on day to day basis and made always available at site and put to the under signed before any bill is submitted to this division for arranging payment.
8. The work should be completed within the comparative cost and stipulated time.

Copy to the: -

1. Deputy Registrar Development/Accounts for information.
2. P.S. to Registrar for information of the Registrar.
3. Concerned
4. Office file